BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Modified Schedule - B

BBMP/2019-20/OW/WORK_INDENT36279

NAME OF WORK:General Public Toilet and Setage Maintenance in Ward No. 14, Dasarahalli Sub Division

Sl. No	Description of work	Unit	Qty	Modified approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	13.37	70.00	Rupees Seventy Only
1	Earthwork in surface excavation in hard soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cabels) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and nearly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Each	13.37	244.84	Rupees Two Hundred Forty Four and Eighty Four Paise Only
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal course aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in laye not exceeding 15cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6.68	5,615.66	Rupees Five Thousand Six Hundred Fifteen and Sixty Six Paise Only
3	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43 cum, with super5plaster @ 3lts confirming to IS9103-1999 Reaffirmed -52008, machine mixed, concrete laid in laye not exceeding 15cms. thick, well compacted, in foundation, plinth and cills, including cost of materials, labours, HOM of machinery, curing complete as per specifications.	Cum	5.78	6,167.66	Rupees Six Thousand One Hundred Sixty Seven and Sixty Six Paise Only
4	Providing and fixing granite benches including cost of materials labours as per sPecifications (Data Rate Approved)	Each	11.00	11,076.45	Rupees Eleven Thousand Seventy Six and Forty Four Paise Only
5	Providing and removing centring, shuttering, strutting,prpping etc.,and removal of form work for vertical surface such as walls at any thickness, including atached pilasters, buttresses, plinth cills and string courses cost of all materials, labours complete as per specifications	sqm	25.74	398.42	Rupees Three Hundred Ninety Eight and Forty Two Paise Only
6	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonary and concrete surface including rounding off corners whereever required smooth rendering,: providing and removing scaffolding, including cost of materials, labours, curing complete as per specifications.	sqm	55.66	301.59	Rupees Three Hundred One and Fifty Nine Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,